


STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☒

APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER GMBU 1-2-9-15H					
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT MONUMENT BUTTE					
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME GMBU (GRRV)					
6. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY						7. OPERATOR PHONE 435 646-4825					
8. ADDRESS OF OPERATOR Rt 3 Box 3630 , Myton, UT, 84052						9. OPERATOR E-MAIL mcrozier@newfield.com					
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) ML-43538			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>					
13. NAME OF SURFACE OWNER (if box 12 = 'fee')						14. SURFACE OWNER PHONE (if box 12 = 'fee')					
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')					
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input checked="" type="checkbox"/>					
20. LOCATION OF WELL	FOOTAGES		QTR-QTR		SECTION	TOWNSHIP		RANGE	MERIDIAN		
LOCATION AT SURFACE	987 FNL 747 FEL		NENE		2	9.0 S		15.0 E	S		
Top of Uppermost Producing Zone	987 FNL 747 FEL		NENE		2	9.0 S		15.0 E	S		
At Total Depth	120 FSL 2350 FEL		SWSE		2	9.0 S		15.0 E	S		
21. COUNTY DUCHESENE			22. DISTANCE TO NEAREST LEASE LINE (Feet) 120			23. NUMBER OF ACRES IN DRILLING UNIT 320					
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 346			26. PROPOSED DEPTH MD: 10472 TVD: 6044					
27. ELEVATION - GROUND LEVEL 5931			28. BOND NUMBER B001834			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 437478					
Hole, Casing, and Cement Information											
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight	
SURF	12.25	8.625	0 - 500	24.0	J-55 ST&C	8.3	Class G	203	1.17	15.8	
PROD	7.875	5.5	0 - 6044	20.0	N-80 LT&C	9.0	Premium Lite High Strength	232	3.53	11.0	
							50/50 Poz	255	1.24	14.3	
ATTACHMENTS											
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES											
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER						<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)						<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)						<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Mandie Crozier				TITLE Regulatory Tech				PHONE 435 646-4825			
SIGNATURE				DATE 07/27/2011				EMAIL mcrozier@newfield.com			
API NUMBER ASSIGNED 43013508980000				APPROVAL  Permit Manager							

RECEIVED: November 22, 2011

Newfield Production Company
Greater Monument Butte 1-2-9-15H
NE/NE Section 2, T9S, R15E
Duchesne County, UT

Drilling Program

1. Formation Tops

Uinta	surface
Green River	1,620'
Garden Gulch member	4,115'
TD	6,044' TVD / 10,472' MD

2. Depth to Oil, Gas, Water, or Minerals

Base of moderately saline	200'	(water)
Green River	4,115' - 6,044'	(oil)

3. Pressure Control

Section BOP Description

Surface No control

Production The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc for a 2M system.

A 2M BOP system will consist of 2 ram preventers (double or two singles), and a rotating head. A choke manifold rated to at least 2,000 psi will be used.

4. Casing

Description	Interval		Weight (ppf)	Grade	Coupl	Pore Press @ Shoe	MW @ Shoe	Frac Grad @ Shoe	Safety Factors		
	Top	Bottom (TVD/MD)							Burst	Collapse	Tension
Surface	0'	500'	24	J-55	STC	8.33	8.33	12	2,950	1,370	244,000
8 5/8									10.52	8.61	20.33
Production	0'	6,044'	20	N-80	LTC	8.33	9.0	--	9,190	8,830	428,000
5 1/2		10,472'							4.56	3.97	3.54

Assumptions:

Surface casing MASP = (frac gradient + 1.0 ppg) - (gas gradient)

Production casing MASP = (reservoir pressure) - (gas gradient)

All collapse calculations assume fully evacuated casing with a gas gradient

All tension calculations assume air weight of casing

Gas gradient = 0.1 psi/ft

All casing shall be new.

All casing strings shall have a minimum of 1 centralizer on each of the bottom 3 joints.

5. Cement

Job	Hole Size	Fill	Slurry Description	ft ³	OH excess	Weight (ppg)	Yield (ft ³ /sk)
				sacks			
Surface	12 1/4	500'	Class G w/ 2% KCl + 0.25 lbs/sk Cello Flake	237	15%	15.8	1.17
				203			
Production Lead	7 7/8	4,115'	Premium Lite II w/ 3% KCl + 10% bentonite	820	15%	11.0	3.53
				232			
Production Tail	7 7/8	1,588'	50/50 Poz/Class G w/ 3% KCl + 2% bentonite	316	15%	14.3	1.24
				255			

The surface casing will be cemented to surface. In the event that cement does not reach surface during the primary cement job, a remedial job will be performed.

A system of open hole packers will be used to isolate frac stages in the lateral. Open hole packers will be used to isolate the vertical portion of the well from the lateral. A port collar will be used to cement the vertical portion of the well.

Actual cement volumes for the production casing string will be calculated from an open hole caliper log, plus 15% excess.

6. Type and Characteristics of Proposed Circulating Medium

<u>Interval</u>	<u>Description</u>
Surface - 500'	An air and/or fresh water system will be utilized. If an air rig is used, the blooie line discharge may be less than 100' from the wellbore in order to minimize location size. The blooie line is not equipped with an automatic igniter. The air compressor may be located less than 100' from the well bore due to the low possibility of combustion with the air/dust mixture. Water will be on location to be used as kill fluid, if necessary.
500' - TD	A water based mud system will be utilized. Hole stability may be improved with additions of KCl or a similar inhibitive substance. In order to control formation pressure the system will be weighted with additions of bentonite, and if conditions warrant, with barite. Anticipated maximum mud weight is 9.0 ppg.

7. Logging, Coring, and Testing

Logging: A dual induction, gamma ray, and caliper log will be run from KOP to the base of the surface casing. A compensated neutron/formation density log will be run from KOP to the top of the Garden Gulch formation. A cement bond log will be run from KOP to the cement top behind the production casing.

Cores: As deemed necessary.

DST: There are no DST's planned for this well.

8. Anticipated Abnormal Pressure or Temperature

Maximum anticipated bottomhole pressure will be approximately equal to total depth (feet) multiplied by a 0.43 psi/ft gradient.

$$6,044' \times 0.43 \text{ psi/ft} = 2618 \text{ psi}$$

No abnormal temperature is expected. No H₂S is expected.

9. Other Aspects

The well will be drilled vertically to a kick-off point of 5,703' .

Directional tools will then be used to build to 91.95 degrees inclination.

The lateral will be drilled to the bottomhole location shown on the plat.


A system of open hole packers will be used to provide multi-stage frac isolation in the lateral.

A set of open hole packers will be placed at kick-off point to isolate the lateral. A port cementing collar will placed above the packers and will be used to cement the vertical portion of the well bore.


CONFIDENTIAL

1-2-9-15H
(Surface Location) NAD 83
LATITUDE = 40° 03' 52.22"
LONGITUDE = 110° 11' 33.31"

DATE SURVEYED: 05-05-11	SURVEYED BY: S.V.	VERSION:
DATE DRAWN: 05-28-11	DRAWN BY: M.W.	V2
REVISED: 07-14-11 F.T.M.	SCALE: 1" = 1000'	



<p>Tri State Land Surveying, Inc. 180 NORTH VERNAL AVE. VERNAL, UTAH 84078</p>		P: (435) 781-2501 F: (435) 781-2518		N 	NEWFIELD EXPLORATION COMPANY 1-2-9-15H SEC. 2, T9S, R15E, S.L.B.&M. Duchesne County, UT.	
		TOPOGRAPHIC MAP			SHEET A	
DRAWN BY: J.A.S. REVISED: 08-15-11 CHM VERSION:		V3				
DATE: 07-01-2011						
SCALE: 1:100,000						



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518




NEWFIELD EXPLORATION COMPANY

1-2-9-15H
SEC. 2, T9S, R15E, S.L.B.&M.
Duchesne County, UT.

DRAWN BY:	J.A.S.	REVISED:	08-15-11 CHM	VERSION:
DATE:	07-01-2011			V3
SCALE:	1" = 2,000'			

TOPOGRAPHIC MAP

SHEET
B



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

**Tri State
Land Surveying, Inc.**
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518




NEWFIELD EXPLORATION COMPANY


**1-2-9-15H
SEC. 2, T9S, R15E, S.L.B.&M.
Duchesne County, UT.**

DRAWN BY:	J.A.S.	REVISED:	08-15-11 CHM	VERSION:
DATE:	07-01-2011			V3
SCALE:	1" = 2,000'			

TOPOGRAPHIC MAP

SHEET
C








<p>Tri State Land Surveying, Inc. 180 NORTH VERNAL AVE. VERNAL, UTAH 84078</p>		<p>P: (435) 781-2501 F: (435) 781-2518</p>		<p>N</p>		<p>NEWFIELD EXPLORATION COMPANY</p> <p>1-2-9-15H SEC. 2, T9S, R15E, S.L.B.&M. Duchesne County, UT.</p>	
		<p>DRAWN BY: J.A.S. REVISED: 08-15-11 CHM VERSION:</p> <p>DATE: 07-01-2011</p> <p>SCALE: 1" = 2,000'</p>		<p>V3</p>		<p>TOPOGRAPHIC MAP</p>	
						<p>SHEET D</p>	



Newfield Production Company

Project: Uinta Basin
Site: GMB 1-2-9-15H
Well: Well #1
Wellbore: Wellbore #1
Design: Design #1



SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	5703.0	0.00	0.00	5703.0	0.0	0.0	0.00	0.00	0.0	
3	6469.3	91.95	200.20	6180.2	-463.3	-170.5	12.00	200.20	493.7	
4	10471.6	91.95	200.20	6044.0	-4217.4	-1551.7	0.00	0.00	4493.8	1-2-9-15H

Created by: Hans Wychgram

Date: 7-26-11

PROJECT DETAILS: Uinta Basin

Geodetic System: US State Plane 1983
 Datum: North American Datum 1983
 Ellipsoid: GRS 1980
 Zone: Utah Central Zone
 System Datum: Mean Sea Level

RECEIVED: July 27, 2011

Newfield Production Company

**Uinta Basin
GMB 1-2-9-15H
Well #1**

Wellbore #1

Plan: Design #1

Standard Planning Report

26 July, 2011

CONFIDENTIAL

Newfield Exploration

Planning Report

Database: EDM 2003.21 Single User Db
Company: Newfield Production Company
Project: Uinta Basin
Site: GMB 1-2-9-15H
Well: Well #1
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well Well #1
TVD Reference: RKB @ 5942.7ft (Capstar #329)
MD Reference: RKB @ 5942.7ft (Capstar #329)
North Reference: True
Survey Calculation Method: Minimum Curvature

Project	Uinta Basin		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Utah Central Zone		

Site	GMB 1-2-9-15H		
Site Position:		Northing:	2,193,008.16m
From:	Lat/Long	Easting:	611,525.62m
Position Uncertainty:	0.0 ft	Slot Radius:	in
		Latitude:	40° 3' 52.220 N
		Longitude:	110° 11' 33.310 W
		Grid Convergence:	0.84 °

Well	Well #1		
Well Position	+N/-S	0.0 ft	Northing: 2,193,008.16 m
	+E/-W	0.0 ft	Easting: 611,525.62 m
Position Uncertainty	0.0 ft	Wellhead Elevation:	ft
		Latitude:	40° 3' 52.220 N
		Longitude:	110° 11' 33.310 W
		Ground Level:	5,930.7 ft

Wellbore	Wellbore #1		
Magnetics	Model Name	Sample Date	Declination (°)
	IGRF200510	12/31/2009	11.54
			Dip Angle (°) 65.83
			Field Strength (nT) 52,435

Design	Design #1		
Audit Notes:			
Version:	Phase:	PROTOTYPE	Tie On Depth: 0.0
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)
	0.0	0.0	0.0
			Direction (°) 200.20

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
5,703.0	0.00	0.00	5,703.0	0.0	0.0	0.00	0.00	0.00	0.00	
6,469.3	91.95	200.20	6,180.2	-463.3	-170.5	12.00	12.00	0.00	200.20	
10,471.6	91.95	200.20	6,044.0	-4,217.4	-1,551.7	0.00	0.00	0.00	0.00	1-2-9-15H

Newfield Exploration

Planning Report

Database:	EDM 2003.21 Single User Db	Local Co-ordinate Reference:	Well Well #1
Company:	Newfield Production Company	TVD Reference:	RKB @ 5942.7ft (Capstar #329)
Project:	Uinta Basin	MD Reference:	RKB @ 5942.7ft (Capstar #329)
Site:	GMB 1-2-9-15H	North Reference:	True
Well:	Well #1	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00
1,600.0	0.00	0.00	1,600.0	0.0	0.0	0.0	0.00	0.00	0.00
1,700.0	0.00	0.00	1,700.0	0.0	0.0	0.0	0.00	0.00	0.00
1,800.0	0.00	0.00	1,800.0	0.0	0.0	0.0	0.00	0.00	0.00
1,900.0	0.00	0.00	1,900.0	0.0	0.0	0.0	0.00	0.00	0.00
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.0	0.00	0.00	0.00
2,100.0	0.00	0.00	2,100.0	0.0	0.0	0.0	0.00	0.00	0.00
2,200.0	0.00	0.00	2,200.0	0.0	0.0	0.0	0.00	0.00	0.00
2,300.0	0.00	0.00	2,300.0	0.0	0.0	0.0	0.00	0.00	0.00
2,400.0	0.00	0.00	2,400.0	0.0	0.0	0.0	0.00	0.00	0.00
2,500.0	0.00	0.00	2,500.0	0.0	0.0	0.0	0.00	0.00	0.00
2,600.0	0.00	0.00	2,600.0	0.0	0.0	0.0	0.00	0.00	0.00
2,700.0	0.00	0.00	2,700.0	0.0	0.0	0.0	0.00	0.00	0.00
2,800.0	0.00	0.00	2,800.0	0.0	0.0	0.0	0.00	0.00	0.00
2,900.0	0.00	0.00	2,900.0	0.0	0.0	0.0	0.00	0.00	0.00
3,000.0	0.00	0.00	3,000.0	0.0	0.0	0.0	0.00	0.00	0.00
3,100.0	0.00	0.00	3,100.0	0.0	0.0	0.0	0.00	0.00	0.00
3,200.0	0.00	0.00	3,200.0	0.0	0.0	0.0	0.00	0.00	0.00
3,300.0	0.00	0.00	3,300.0	0.0	0.0	0.0	0.00	0.00	0.00
3,400.0	0.00	0.00	3,400.0	0.0	0.0	0.0	0.00	0.00	0.00
3,500.0	0.00	0.00	3,500.0	0.0	0.0	0.0	0.00	0.00	0.00
3,600.0	0.00	0.00	3,600.0	0.0	0.0	0.0	0.00	0.00	0.00
3,700.0	0.00	0.00	3,700.0	0.0	0.0	0.0	0.00	0.00	0.00
3,800.0	0.00	0.00	3,800.0	0.0	0.0	0.0	0.00	0.00	0.00
3,900.0	0.00	0.00	3,900.0	0.0	0.0	0.0	0.00	0.00	0.00
4,000.0	0.00	0.00	4,000.0	0.0	0.0	0.0	0.00	0.00	0.00
4,100.0	0.00	0.00	4,100.0	0.0	0.0	0.0	0.00	0.00	0.00
4,200.0	0.00	0.00	4,200.0	0.0	0.0	0.0	0.00	0.00	0.00
4,300.0	0.00	0.00	4,300.0	0.0	0.0	0.0	0.00	0.00	0.00
4,400.0	0.00	0.00	4,400.0	0.0	0.0	0.0	0.00	0.00	0.00
4,500.0	0.00	0.00	4,500.0	0.0	0.0	0.0	0.00	0.00	0.00
4,600.0	0.00	0.00	4,600.0	0.0	0.0	0.0	0.00	0.00	0.00
4,700.0	0.00	0.00	4,700.0	0.0	0.0	0.0	0.00	0.00	0.00
4,800.0	0.00	0.00	4,800.0	0.0	0.0	0.0	0.00	0.00	0.00
4,900.0	0.00	0.00	4,900.0	0.0	0.0	0.0	0.00	0.00	0.00
5,000.0	0.00	0.00	5,000.0	0.0	0.0	0.0	0.00	0.00	0.00
5,100.0	0.00	0.00	5,100.0	0.0	0.0	0.0	0.00	0.00	0.00
5,200.0	0.00	0.00	5,200.0	0.0	0.0	0.0	0.00	0.00	0.00
5,300.0	0.00	0.00	5,300.0	0.0	0.0	0.0	0.00	0.00	0.00

Newfield Exploration

Planning Report

Database:	EDM 2003.21 Single User Db	Local Co-ordinate Reference:	Well Well #1
Company:	Newfield Production Company	TVD Reference:	RKB @ 5942.7ft (Capstar #329)
Project:	Uinta Basin	MD Reference:	RKB @ 5942.7ft (Capstar #329)
Site:	GMB 1-2-9-15H	North Reference:	True
Well:	Well #1	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	
5,400.0	0.00	0.00	5,400.0	0.0	0.0	0.0	0.00	0.00	0.00	
5,500.0	0.00	0.00	5,500.0	0.0	0.0	0.0	0.00	0.00	0.00	
5,600.0	0.00	0.00	5,600.0	0.0	0.0	0.0	0.00	0.00	0.00	
5,700.0	0.00	0.00	5,700.0	0.0	0.0	0.0	0.00	0.00	0.00	
5,703.0	0.00	0.00	5,703.0	0.0	0.0	0.0	0.00	0.00	0.00	
5,800.0	11.64	200.20	5,799.3	-9.2	-3.4	9.8	12.00	12.00	0.00	
5,900.0	23.64	200.20	5,894.5	-37.6	-13.8	40.1	12.00	12.00	0.00	
6,000.0	35.64	200.20	5,981.2	-83.9	-30.9	89.4	12.00	12.00	0.00	
6,100.0	47.64	200.20	6,055.8	-146.2	-53.8	155.8	12.00	12.00	0.00	
6,200.0	59.64	200.20	6,115.0	-221.6	-81.5	236.1	12.00	12.00	0.00	
6,300.0	71.64	200.20	6,156.2	-307.0	-112.9	327.1	12.00	12.00	0.00	
6,400.0	83.64	200.20	6,177.5	-398.5	-146.6	424.6	12.00	12.00	0.00	
6,469.3	91.95	200.20	6,180.2	-463.3	-170.5	493.7	12.00	12.00	0.00	
6,500.0	91.95	200.20	6,179.1	-492.2	-181.1	524.4	0.00	0.00	0.00	
6,600.0	91.95	200.20	6,175.7	-586.0	-215.6	624.4	0.00	0.00	0.00	
6,700.0	91.95	200.20	6,172.3	-679.8	-250.1	724.3	0.00	0.00	0.00	
6,800.0	91.95	200.20	6,168.9	-773.6	-284.6	824.3	0.00	0.00	0.00	
6,900.0	91.95	200.20	6,165.5	-867.4	-319.1	924.2	0.00	0.00	0.00	
7,000.0	91.95	200.20	6,162.1	-961.2	-353.6	1,024.2	0.00	0.00	0.00	
7,100.0	91.95	200.20	6,158.7	-1,055.0	-388.1	1,124.1	0.00	0.00	0.00	
7,200.0	91.95	200.20	6,155.3	-1,148.8	-422.7	1,224.0	0.00	0.00	0.00	
7,300.0	91.95	200.20	6,151.9	-1,242.5	-457.2	1,324.0	0.00	0.00	0.00	
7,400.0	91.95	200.20	6,148.5	-1,336.3	-491.7	1,423.9	0.00	0.00	0.00	
7,500.0	91.95	200.20	6,145.1	-1,430.1	-526.2	1,523.9	0.00	0.00	0.00	
7,600.0	91.95	200.20	6,141.7	-1,523.9	-560.7	1,623.8	0.00	0.00	0.00	
7,700.0	91.95	200.20	6,138.3	-1,617.7	-595.2	1,723.7	0.00	0.00	0.00	
7,800.0	91.95	200.20	6,134.9	-1,711.5	-629.7	1,823.7	0.00	0.00	0.00	
7,900.0	91.95	200.20	6,131.5	-1,805.3	-664.2	1,923.6	0.00	0.00	0.00	
8,000.0	91.95	200.20	6,128.1	-1,899.1	-698.7	2,023.6	0.00	0.00	0.00	
8,100.0	91.95	200.20	6,124.7	-1,992.9	-733.2	2,123.5	0.00	0.00	0.00	
8,200.0	91.95	200.20	6,121.3	-2,086.7	-767.8	2,223.5	0.00	0.00	0.00	
8,300.0	91.95	200.20	6,117.9	-2,180.5	-802.3	2,323.4	0.00	0.00	0.00	
8,400.0	91.95	200.20	6,114.5	-2,274.3	-836.8	2,423.3	0.00	0.00	0.00	
8,500.0	91.95	200.20	6,111.1	-2,368.1	-871.3	2,523.3	0.00	0.00	0.00	
8,600.0	91.95	200.20	6,107.7	-2,461.9	-905.8	2,623.2	0.00	0.00	0.00	
8,700.0	91.95	200.20	6,104.3	-2,555.7	-940.3	2,723.2	0.00	0.00	0.00	
8,800.0	91.95	200.20	6,100.9	-2,649.5	-974.8	2,823.1	0.00	0.00	0.00	
8,900.0	91.95	200.20	6,097.5	-2,743.3	-1,009.3	2,923.1	0.00	0.00	0.00	
9,000.0	91.95	200.20	6,094.1	-2,837.1	-1,043.8	3,023.0	0.00	0.00	0.00	
9,100.0	91.95	200.20	6,090.7	-2,930.9	-1,078.3	3,122.9	0.00	0.00	0.00	
9,200.0	91.95	200.20	6,087.3	-3,024.6	-1,112.9	3,222.9	0.00	0.00	0.00	
9,300.0	91.95	200.20	6,083.9	-3,118.4	-1,147.4	3,322.8	0.00	0.00	0.00	
9,400.0	91.95	200.20	6,080.5	-3,212.2	-1,181.9	3,422.8	0.00	0.00	0.00	
9,500.0	91.95	200.20	6,077.1	-3,306.0	-1,216.4	3,522.7	0.00	0.00	0.00	
9,600.0	91.95	200.20	6,073.7	-3,399.8	-1,250.9	3,622.6	0.00	0.00	0.00	
9,700.0	91.95	200.20	6,070.3	-3,493.6	-1,285.4	3,722.6	0.00	0.00	0.00	
9,800.0	91.95	200.20	6,066.9	-3,587.4	-1,319.9	3,822.5	0.00	0.00	0.00	
9,900.0	91.95	200.20	6,063.5	-3,681.2	-1,354.4	3,922.5	0.00	0.00	0.00	
10,000.0	91.95	200.20	6,060.0	-3,775.0	-1,388.9	4,022.4	0.00	0.00	0.00	
10,100.0	91.95	200.20	6,056.6	-3,868.8	-1,423.4	4,122.4	0.00	0.00	0.00	
10,200.0	91.95	200.20	6,053.2	-3,962.6	-1,458.0	4,222.3	0.00	0.00	0.00	
10,300.0	91.95	200.20	6,049.8	-4,056.4	-1,492.5	4,322.2	0.00	0.00	0.00	
10,400.0	91.95	200.20	6,046.4	-4,150.2	-1,527.0	4,422.2	0.00	0.00	0.00	
10,471.6	91.95	200.20	6,044.0	-4,217.4	-1,551.7	4,493.8	0.00	0.00	0.00	

NEWFIELD PRODUCTION COMPANY
GMBU 1-2-9-15H
SHL: NE/NE SECTION 2, T9S, R15E
BHL: SW/SE SECTION 2, T9S, R15E
DUCHESNE COUNTY, UTAH

THIRTEEN POINT SURFACE PROGRAM

1. **EXISTING ROADS**

See attached **Topographic Map "A"**

To reach Newfield Production Company well location site GMBU 1-2-9-15H located in the NE¼ NE¼ Section 2, T9S, R15E, S.L.B. & M., Duchesne County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 - 1.4 miles ± to the junction of this highway and UT State Hwy 53; proceed southwesterly - 4.7 miles ± to its junction with an existing road to the southwest; proceed southwesterly - 2.4 miles ± to its junction with an existing road to the southwest; proceed southwesterly - 0.8 miles ± to its junction with an existing road to the east; proceed in a southeasterly direction - 1.6 miles ± to its junction with an existing road to the southwest; proceed southwesterly - 0.9 miles ± to its junction with an existing road to the north; proceed northwesterly - 0.1 miles ± to its junction with the beginning of the access road to the northeast; proceed northeasterly along the proposed access road - 557' ± to the proposed well location.

The highways mentioned in the foregoing paragraph are bituminous surfaced roads to the point where Highway 216 exists to the South, thereafter the roads are constructed with existing materials and gravel. The highways are maintained by Utah State road crews. All other roads are maintained by County crews.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal.

2. **PLANNED ACCESS ROAD**

Approximately 557' of access road is proposed. See attached **Topographic Map "B"**.

The proposed access road will be an 18' crown road (9' either side of the centerline) with drainage ditches along either side of the proposed road whether it is deemed necessary in order to handle any run-off from normal meteorological conditions that are prevalent to this area. The maximum grade will be less than 8%.

There will be no culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

3. **LOCATION OF EXISTING WELLS**

Refer to **EXHIBIT B**.

4. **LOCATION OF EXISTING AND/OR PROPOSED FACILITIES**

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within six months of installation.

5. **LOCATION AND TYPE OF WATER SUPPLY**

Newfield Production will transport water by truck for drilling purposes from the following water sources:

Johnson Water District
Water Right: 43-7478

Neil Moon Pond
Water Right: 43-11787

Maurice Harvey Pond
Water Right: 47-1358

Newfield Collector Well
Water Right: 47-1817 (A30414DVA, contracted with the Duchesne County Conservancy District).

There will be no water well drilled at this site

6. **SOURCE OF CONSTRUCTION MATERIALS**

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous

will be placed in this pit. A 16 mil liner with felt will be required. Newfield requests approval that a flare pit be constructed and utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

Immediately upon first production, all produced water will be confined to a steel storage tank. If the production water meets quality guidelines, it is transported to the Ashley, Monument Butte, Jonah, and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project.

Water not meeting quality criteria, is disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E) or at State of Utah approved surface disposal facilities.

8. **ANCILLARY FACILITIES:**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT:**

See attached Location Layout Sheet.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

10. **PLANS FOR RESTORATION OF SURFACE:**

a) **Producing Location**

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

b) **Dry Hole Abandoned Location**

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. **SURFACE OWNERSHIP:** State of Utah.

12. **OTHER ADDITIONAL INFORMATION:**

The Archaeological Resource Survey and Paleontological Resource Survey for this area are attached. State of Utah Antiquities Project Permit #U-99-JB-0331bs 3/27/00, prepared by JBR Environmental Consultants Inc.. Paleontological Resource Survey prepared by, Wade E. Miller, 7/28/03. See attached report cover pages, Exhibit "D".

Newfield Production Company requests 557' of planned access road to be granted. **Refer to Topographic Map "B".**

Surface Flow Line

Newfield requests 1,026' of surface flow line be granted. The Surface Flow Line will consist of up to a 14" bundled pipe consisting of 2-2" poly glycol lines and 1-3" production line. For all new wells, Newfield. Refer to Topographic Map "C" for the proposed location of the proposed flow line. Flow lines will be tan and will be constructed using the following procedures:

Clearing and Grading: No clearing or grading of the ROW will be required. The centerline of the proposed route will be staked prior to installation. Flow lines shall be placed as close to existing roads as possible without interfering with normal road travel or road maintenance activities. Due to the proximity of existing facilities, no temporary use or construction/storage areas are anticipated. If necessary, temporary use or construction/storage areas will be identified on a topographic map included in the approved permit.

Installation: The proposed flow lines will be installed 4-6" above the ground. For portions along existing two-track and primary access roads, lengths of pipe will be strung out in the borrow ditch, welded together, and rolled or dragged into place with heavy equipment. For pipelines that are installed cross-country (not along existing or proposed roads), travel along the lines will be infrequent and for maintenance needs only. No installation activities will be performed during periods when the soil is too wet to adequately support installation equipment. If such equipment creates ruts in excess of three (3) inches deep, the soil will be deemed too wet to adequately support the equipment.

Termination and Final Reclamation: After abandonment of the associated production facilities, the flow lines will be cut and removed, and any incidental surface disturbance reclaimed. Reclamation procedures will follow those outlined in the Castle Peak and Eight Mile Flat Reclamation and Weed Management Plan.

a) Newfield Production Company is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, Newfield is to immediately stop work that might further disturb such materials and contact the Authorized Officer.

- b) Newfield Production will control noxious weeds along rights-of-way for roads, pipelines, well sites or other applicable facilities. On State administered land it is required that a Pesticide Use Proposal shall be submitted and given approval prior to the application of herbicides or other possible hazardous chemicals.
- c) Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on State Lands after the conclusion of drilling operations or at any other time without State authorization. However, if State authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities.

Water Disposal

After first production, if the production water meets quality guidelines, it will be transported to the Ashley, Monument Butte, Jonah, South Wells Draw and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project. Water not meeting quality criteria, will be disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E), Federally approved surface disposal facilities or at a State of Utah approved surface disposal facilities.

Additional Surface Stipulations

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

Hazardous Material Declaration

Newfield Production Company guarantees that during the drilling and completion of the GMBU 1-2-9-15H, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the GMBU 1-2-9-15H Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

The State office shall be notified upon site completion prior to moving on the drilling rig.

13. LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:

Representative

Name: Tim Eaton
Address: Newfield Production Company
Route 3, Box 3630
Myton, UT 84052
Telephone: (435) 646-3721

Certification

Please be advised that Newfield Production Company is considered to be the operator of well #1-2-9-15H, NE/NE Section 2, T9S, R15E, Duchesne County, Utah and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Bond #B001834.


I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.

_____/7/27/11_____
Date

Mandie Crozier
Regulatory Analyst
Newfield Production Company

CONFIDENTIAL

Typical 2M BOP stack configuration



NEWFIELD EXPLORATION COMPANY

WELL PAD INTERFERENCE PLAT

1-2-9-15H (Proposed Well)

Pad Location: NENE (Lot 1) Section 2, T9S, R15E, S.L.B.&M.



TOP HOLE FOOTAGES

1-2-9-15H (PROPOSED)
987' FNL & 747' FEL

Edge of Existing 1-2-9-15 Pad
Existing 3" Valve
Existing 4" Valve
Existing 3" Polyline
Existing 4" Polyline

Future Pit

1-2-9-15H (PROPOSED)

BOTTOM HOLE FOOTAGES

1-2-9-15H (PROPOSED)
120' FSL & 2350' FEL

S20°12'01"W - 4493.76'
(To Bottom Hole)

Proposed Access

RELATIVE COORDINATES From Top Hole to Bottom Hole

WELL	NORTH	EAST
1-2-9-15H	-4,217'	-1,552'

LATITUDE & LONGITUDE Surface position of Wells (NAD 83)

WELL	LATITUDE	LONGITUDE
1-2-9-15H	40° 03' 52.22"	110° 11' 33.31"

Note:

Bearings are based
on GPS Observations.

SURVEYED BY: S.V.	DATE SURVEYED: 05-05-11	VERSION:
DRAWN BY: M.W.	DATE DRAWN: 05-27-11	V3
SCALE: 1" = 60'	REVISED: F.T.M. 08-15-11	

Tri State
Land Surveying, Inc.

(435) 781-2501


180 NORTH VERNAL AVE. VERNAL, UTAH 84078

NEWFIELD EXPLORATION COMPANY

LOCATION LAYOUT

1-2-9-15H (Proposed Well)

Pad Location: NENE (Lot 1) Section 2, T9S, R15E, S.L.B.&M.



SURVEYED BY: S.V.	DATE SURVEYED: 05-05-11	VERSION:
DRAWN BY: F.T.M.	DATE DRAWN: 05-28-11	V3
SCALE: 1" = 60'	REVISED: F.T.M. 08-15-11	





Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078
(435) 781-2501

NEWFIELD EXPLORATION COMPANY

CROSS SECTIONS

1-2-9-15H (Proposed Well)

Pad Location: NENE (Lot 1) Section 2, T9S, R15E, S.L.B.&M.



NOTE:
UNLESS OTHERWISE
NOTED ALL CUT/FILL
SLOPES ARE AT 1.5:1

ESTIMATED EARTHWORK QUANTITIES (No Shrink or swell adjustments have been used) (Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	13,420	13,420	Topsoil is not included in Pad Cut	0
PIT	4,100	0		4,100
TOTALS	17,520	13,420	2,320	4,100

SURVEYED BY: S.V.

DATE SURVEYED: 05-05-11

VERSION:

DRAWN BY: F.T.M.

DATE DRAWN: 05-28-11

V3

SCALE: 1" = 60'

REVISED: F.T.M. 08-15-11

Tri State
Land Surveying, Inc.

(435) 781-2501


180 NORTH VERNAL AVE. VERNAL, UTAH 84078

NEWFIELD EXPLORATION COMPANY


TYPICAL RIG LAYOUT

1-2-9-15H (Proposed Well)

Pad Location: NENE (Lot 1) Section 2, T9S, R15E, S.L.B.&M.




SURVEYED BY: S.V.	DATE SURVEYED: 05-05-11	VERSION:	Tri State Land Surveying, Inc. 180 NORTH VERNAL AVE. VERNAL, UTAH 84078	(435) 781-2501
DRAWN BY: F.T.M.	DATE DRAWN: 05-28-11	V3		
SCALE: 1" = 60'	REVISED: F.T.M. 08-15-11			



API Number: 4301350898
Well Name: GMBU 1-2-9-15H
Township T0.9 . Range R1.5 . Section 02
Meridian: SLBM
Operator: NEWFIELD PRODUCTION COMPANY

Map Prepared:
 Map Produced by Diana Mason

Units	Wells Query
STATUS	STATUS
ACTIVE	APD - Approved Permit
EXPLORATORY	DRL - Spudded (Drilling Commenced)
GAS STORAGE	GIW - Gas Injection
NF PP OIL	GS - Gas Storage
NF SECONDARY	LA - Location Abandoned
PI OIL	LOC - New Location
PP GAS	OPS - Operation Suspended
PP GEOTHERMAL	PA - Plugged Abandoned
PP OIL	PGW - Producing Gas Well
SECONDARY	POW - Producing Oil Well
TERMINATED	RET - Returned APD
Fields	SGW - Shut-in Gas Well
Unknown	SOW - Shut-in Oil Well
ABANDONED	TA - Temp. Abandoned
ACTIVE	TW - Test Well
COMBINED	WDW - Water Disposal
INACTIVE	WIW - Water Injection Well
STORAGE	WSW - Water Supply Well
TERMINATED	
Sections	
Township	



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:
3160
(UT-922)

July 29, 2011

Memorandum

To: Assistant District Manager Minerals, Vernal District
From: Michael Coulthard, Petroleum Engineer
Subject: 2011 Plan of Development Greater Monument
Butte Unit, Duchesne and Uintah Counties,
Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2011 within the Greater Monument Butte Unit, Duchesne and Uintah Counties, Utah.

API #	WELL NAME	LOCATION
(Proposed PZ GREEN RIVER)		
43-013-50891	GMBU 2-22-8-16	Sec 22 T08S R16E 0772 FNL 1939 FEL
43-013-50898	GMBU 1-2-9-15H	Sec 02 T09S R15E 0987 FNL 0747 FEL
	Lateral 1	Sec 02 T09S R15E 0120 FSL 2350 FEL
43-047-51752	GMBU 1-2T-9-17H	Sec 02 T09S R17E 0456 FNL 1059 FEL
	Lateral 1	Sec 02 T09S R17E 0100 FSL 2644 FEL

This office has no objection to permitting the wells at this time.

Michael L. Coulthard

Digitally signed by Michael L. Coulthard
DN: cn=Michael L. Coulthard, o=Bureau of Land Management,
ou=Branch of Minerals, email=Michael_Coulthard@blm.gov, c=US
Date: 2011.07.29 09:01:33 -06'00'

bcc: File - Greater Monument Butte Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron



MCoulthard:mc:7-29-11

RECEIVED: August 01, 2011



Newfield Production Company

Project: Uinta Basin
Site: GMB 1-2-9-15H
Well: Well #1
Wellbore: Wellbore #1
Design: Design #1



SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	5703.0	0.00	0.00	5703.0	0.0	0.0	0.00	0.00	0.0	
3	6469.3	91.95	200.20	6180.2	-463.3	-170.5	12.00	200.20	493.7	
4	10471.6	91.95	200.20	6044.0	-4217.4	-1551.7	0.00	0.00	4493.8	1-2-9-15H

PROJECT DETAILS: Uinta Basin

Geodetic System: US State Plane 1983
Datum: North American Datum 1983
Ellipsoid: GRS 1980
Zone: Utah Central Zone
System Datum: Mean Sea Level

Created by: Hans Wychgram



Date: 7-26-11



Newfield Production Company

Project: Uinta Basin
Site: GMB 1-2T-9-17H
Well: Well #1
Wellbore: Wellbore #1
Design: Design #1

Azimuths to True North
Magnetic North: 11.45°
Magnetic Field
Strength: 52474.6snT
Dip Angle: 65.88°
Date: 12/31/2009
Model: IGRF200510



SECTION DETAILS									
Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0
2	5525.9	0.00	0.00	5525.9	0.0	0.0	0.00	0.00	0.0
3	6295.1	92.30	197.60	6003.0	-473.4	-150.2	12.00	197.60	496.7
410797.6	92.30	197.60	197.60	5822.0	-4761.7	-1510.4	0.00	0.00	4995.5

PROJECT DETAILS: Uinta Basin
Geodetic System: US State Plane 1983
Datum: North American Datum 1983
Ellipsoid: GRS 1980
Zone: Utah Central Zone
System Datum: Mean Sea Level

Created by: Hans Wychgram
Date: 7-26-11

Well Name	NEWFIELD PRODUCTION COMPANY GMBU 1-2-9-15H 4301			
String	Surf	Prod		
Casing Size(in)	8.625	5.500		
Setting Depth (TVD)	500	6044		
Previous Shoe Setting Depth (TVD)	0	500		
Max Mud Weight (ppg)	8.3	9.0		
BOPE Proposed (psi)	500	2000		
Casing Internal Yield (psi)	2950	9190		
Operators Max Anticipated Pressure (psi)	2599	8.3		

Calculations	Surf String	8.625	"
Max BHP (psi)	.052*Setting Depth*MW=	216	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	156	YES air drill
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	106	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	106	NO OK
Required Casing/BOPE Test Pressure=		500	psi
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi *Assumes 1psi/ft frac gradient

Calculations	Prod String	5.500	"
Max BHP (psi)	.052*Setting Depth*MW=	2829	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	2104	NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	1499	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	1609	NO Reasonable for area
Required Casing/BOPE Test Pressure=		2000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		500	psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BHP (psi)	.052*Setting Depth*MW=		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BHP (psi)	.052*Setting Depth*MW=		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO
Required Casing/BOPE Test Pressure=			psi

API Well Number: 43013508980000

*Max Pressure Allowed @ Previous Casing Shoe=


psi *Assumes 1psi/ft frac gradient

CONFIDENTIAL

RECEIVED: September 14, 2011

43013508980000 GMBU 1-2-9-15H

Casing Schematic



Well name:	43013508980000 GMBU 1-2-9-15H	
Operator:	NEWFIELD PRODUCTION COMPANY	
String type:	Surface	Project ID: 43-013-50898
Location:	DUCESNE COUNTY	

Design parameters:**Collapse**

Mud weight: 8.330 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 81 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft
Cement top: 176 ft

Burst

Max anticipated surface pressure: 440 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 500 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on air weight.
Neutral point: 437 ft

Non-directional string.**Re subsequent strings:**

Next setting depth: 6,044 ft
Next mud weight: 9.000 ppg
Next setting BHP: 2,826 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 500 ft
Injection pressure: 500 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	500	8.625	24.00	J-55	ST&C	500	500	7.972	2573
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	216	1370	6.333	500	2950	5.90	12	244	20.34 J

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: August 18, 2011
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 500 ft, a mud weight of 8.33 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	43013508980000 GMBU 1-2-9-15H	
Operator:	NEWFIELD PRODUCTION COMPANY	
String type:	Production	Project ID: 43-013-50898
Location:	DUCHESE COUNTY	

Design parameters:**Collapse**

Mud weight: 9.000 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 159 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 4,616 ft

Burst

Max anticipated surface pressure: 1,496 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 2,826 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Tension is based on air weight.
Neutral point: 5,221 ft

Directional Info - Build & Hold

Kick-off point: 5703 ft
Departure at shoe: 4494 ft
Maximum dogleg: 12 °/100ft
Inclination at shoe: 91.95 °

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	10472	5.5	20.00	N-80	LT&C	6044	10472	4.653	69461
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	2826	8830	3.125	2855	9190	3.22	120.9	428	3.54 J

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: August 18, 2011
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 6044 ft, a mud weight of 9 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

From: Jim Davis
To: Hill, Brad; Mason, Diana
CC: Bonner, Ed; Garrison, LaVonne; mcrozier@newfield.com; teaton@newfield...
Date: 9/20/2011 3:45 PM
Subject: Newfield APD approvals

The following APDs have been approved by SITLA including arch and paleo clearance.

4304751877	GMBU I-32-8-18
4304751878	GMBU H-32-8-18
4304751879	GMBU L-32-8-18
4304751880	GMBU R-32-8-18
4304751881	GMBU M-32-8-18
4304751882	GMBU G-32-8-18
4304751883	GMBU N-32-8-18
4304751884	GMBU S-32-8-18
4301350898	GMBU 1-2-9-15H
4301350906	GMBU R-2-9-15
4301350907	GMBU L-2-9-15
4301350908	GMBU H-2-9-15
4301350909	GMBU M-2-9-15
4301350910	GMBU N-2-9-15
4301350911	GMBU Q-2-9-15

Thanks.

-Jim

Jim Davis
Utah Trust Lands Administration
jimdavis1@utah.gov
Phone: (801) 538-5156

CONFIDENTIAL

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator	NEWFIELD PRODUCTION COMPANY				
Well Name	GMBU 1-2-9-15H				
API Number	43013508980000	APD No	4261	Field/Unit	MONUMENT BUTTE
Location: 1/4,1/4	NENE	Sec	2	Tw	9.0S
		Rng	15.0E	987	FNL 747 FEL
GPS Coord (UTM)	Surface Owner				

Participants

M. Jones (UDOGM), T. Eaton (Newfield), J. Davis (SITLA), A. Hansen (DWR).

Regional/Local Setting & Topography

This location is proposed approximately 14 road miles southwest of Myton, Utah. The topography is rolling hills and dry wash drainages. This is a proposed horizontal well with the bottom of the hole southwest of the surface location. As staked for the plats and pre-site this location has some drainage issues. It was ultimately suggested that the location could be rotated clockwise around the drill stake some to avoid some of the drainage issues. SITLA and Newfield agreed with the suggestion. SITLA and DOGM asked if this well could be drilled off of existing disturbance right next door at the 1-2-9-15 well. It would take extensive work to make that existing location work with the new pad needs.

Surface Use Plan

Current Surface Use

Grazing
Wildlife Habitat

New Road Miles	Well Pad	Src Const Material	Surface Formation
0	Width 200 Length 400	Onsite	

Ancillary Facilities

Waste Management Plan Adequate?

Environmental Parameters

Affected Floodplains and/or Wetlands N

Flora / Fauna

sagebrush, 4 wing, grasses.

Soil Type and Characteristics

gravely clay

Erosion Issues Y

Location has some drainage issues that could pose erosion problems.

Sedimentation Issues N

Site Stability Issues Y

Stability could be an issue in fill portions of pad excavation. Should be okay with compaction during excavation.

Drainage Diversion Required? Y

Divert drainages around and away from location and road.

Berm Required? Y

Berm location to prevent fluids from entering and/or leaving the pad.

Erosion Sedimentation Control Required? N**Paleo Survey Run? N Paleo Potential Observed? N Cultural Survey Run? N Cultural Resources? N****Reserve Pit****Site-Specific Factors****Site Ranking**

Distance to Groundwater (feet)	>200	0
Distance to Surface Water (feet)	>1000	0
Dist. Nearest Municipal Well (ft)	>5280	0
Distance to Other Wells (feet)		20
Native Soil Type	High permeability	20
Fluid Type	Air/mist	0
Drill Cuttings	Normal Rock	0
Annual Precipitation (inches)	10 to 20	5
Affected Populations		
Presence Nearby Utility Conduits	Not Present	0
Final Score		45

1 Sensitivity Level

Characteristics / Requirements

Dugout earthen (165' x 100' x 8') excluded from pad dimensions.

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 16 Pit Underlayment Required? N**Other Observations / Comments**Mark Jones
Evaluator8/10/2011
Date / Time

Application for Permit to Drill Statement of Basis

11/22/2011

Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
4261	43013508980000	LOCKED	OW	S	No
Operator	NEWFIELD PRODUCTION COMPANY		Surface Owner-APD		
Well Name	GMBU 1-2-9-15H		Unit	GMBU (GRRV)	
Field	MONUMENT BUTTE		Type of Work	DRILL	
Location	NENE 2 9S 15E S 987 FNL 747 FEL		GPS Coord (UTM)	568844E	4435233N

Geologic Statement of Basis

Newfield proposes to set 500 feet of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 200'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 2. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The proposed casing and cement should adequately protect useable sources of underground water.

Brad Hill
APD Evaluator

8/16/2011
Date / Time

Surface Statement of Basis

This location is proposed approximately 14 road miles southwest of Myton, Utah. The topography is rolling hills and dry wash drainages. This is a proposed horizontal well with the bottom of the hole southwest of the surface location. As staked for the plats and pre-site this location has some drainage issues. It was ultimately suggested that the location could be rotated clockwise around the drill stake some to avoid some of the drainage issues. SITLA and Newfield agreed with the suggestion. SITLA and DOGM asked if this well could be drilled off of existing disturbance right next door at the 1-2-9-15 well. It would take extensive work to make that existing location work with the new pad needs. The location was restaked showing a clockwise rotation and was looked at by Mark Jones (UDOGM) and Tim Eaton (Newfield) on August 31, 2011. Plats were provided at that time for the inspection and will need to be submitted to the Division to be included with the APD package.

Mark Jones
Onsite Evaluator

8/10/2011
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils shall be properly installed and maintained in the reserve pit.
Surface	The well site shall be bermed to prevent fluids from leaving the pad.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location.
Surface	The reserve pit shall be fenced upon completion of drilling operations.
Surface	Rotate the well pad clockwise around the center stake to pull pad out of drainages some on the south. New plats should be submitted showing this prior to APD approval.

RECEIVED: November 22, 2011

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 7/27/2011

API NO. ASSIGNED: 43013508980000

WELL NAME: GMBU 1-2-9-15H

OPERATOR: NEWFIELD PRODUCTION COMPANY (N2695)

PHONE NUMBER: 435 646-4825

CONTACT: Mandie Crozier

PROPOSED LOCATION: NENE 02 090S 150E

Permit Tech Review: ☒

SURFACE: 0987 FNL 0747 FEL

Engineering Review: ☒

BOTTOM: 0120 FSL 2350 FEL

Geology Review: ☒

COUNTY: DUCHESNE

LATITUDE: 40.06454

LONGITUDE: -110.19273

UTM SURF EASTINGS: 568844.00

NORTHINGS: 4435233.00

FIELD NAME: MONUMENT BUTTE

LEASE TYPE: 3 - State

LEASE NUMBER: ML-43538

PROPOSED PRODUCING FORMATION(S): GREEN RIVER

SURFACE OWNER: 3 - State

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

- ☒ PLAT
- ☒ Bond: STATE - B001834
- ☐ Potash
- ☐ Oil Shale 190-5
- ☐ Oil Shale 190-3
- ☐ Oil Shale 190-13
- ☒ Water Permit: 437478
- ☐ RDCC Review:
- ☐ Fee Surface Agreement
- ☐ Intent to Commingle
- Commingle Approved

LOCATION AND SITING:


- ☐ R649-2-3.
- Unit: GMBU (GRRV)
- ☐ R649-3-2. General
- ☐ R649-3-3. Exception
- ☒ Drilling Unit
- Board Cause No: Cause 213-11
- Effective Date: 11/30/2009
- Siting: Suspends General Siting
- ☒ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations:

- 5 - Statement of Basis - bhill
- 8 - Cement to Surface -- 2 strings - hmadonald
- 15 - Directional - dmason
- 27 - Other - bhill
- 28 - Other2 - bhill

RECEIVED: November 22, 2011



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: GMBU 1-2-9-15H
API Well Number: 43013508980000
Lease Number: ML-43538
Surface Owner: STATE
Approval Date: 11/22/2011

Issued to:

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

Authority:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 213-11. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Production casing cement shall be brought up to or above the top of the unitized interval for the Greater Monument Butte Unit (Cause No. 213-11).

Cement volumes for the 8 5/8" and 5 1/2" casing strings shall be determined from actual hole diameters in order to place cement from the pipe setting depths back to the surface.

In accordance with Utah Admin. R.649-3-21, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before

performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan – contact Dustin Doucet
- Significant plug back of the well – contact Dustin Doucet
- Plug and abandonment of the well – contact Dustin Doucet

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels
OR
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program – contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well – contact Dan Jarvis

Contact Information:

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office
801-231-8956 - after office hours

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

Approved By:



For John Rogers
Associate Director, Oil & Gas

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	5. LEASE DESIGNATION AND SERIAL NUMBER: ML-43538
1. TYPE OF WELL Oil Well	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY	7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052	8. WELL NAME and NUMBER: GMBU 1-2-9-15H
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0987 FNL 0747 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 02 Township: 09.0S Range: 15.0E Meridian: S	9. API NUMBER: 43013508980000
PHONE NUMBER: 435 646-4825 Ext	9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
COUNTY: DUCHESNE	STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 11/22/2012	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> OTHER
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input checked="" type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> SPUD REPORT Date of Spud:	
<input type="checkbox"/> DRILLING REPORT Report Date:	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Newfield proposes to extend the Application for Permit to Drill for one year.

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: November 13, 2012

By: 

NAME (PLEASE PRINT) Mandie Crozier	PHONE NUMBER 435 646-4825	TITLE Regulatory Tech
SIGNATURE N/A	DATE 11/8/2012	



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43013508980000

API: 43013508980000

Well Name: GMBU 1-2-9-15H

Location: 0987 FNL 0747 FEL QTR NENE SEC 02 TWNP 090S RNG 150E MER S

Company Permit Issued to: NEWFIELD PRODUCTION COMPANY

Date Original Permit Issued: 11/22/2011

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Mandie Crozier

Date: 11/8/2012

Title: Regulatory Tech **Representing:** NEWFIELD PRODUCTION COMPANY

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-43538
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: GMBU 1-2-9-15H
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0987 FNL 0747 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 02 Township: 09.0S Range: 15.0E Meridian: S		9. API NUMBER: 43013508980000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
COUNTY: DUCHESNE		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 11/22/2013	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> APD EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> OTHER
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> SPUD REPORT Date of Spud:	
<input type="checkbox"/> DRILLING REPORT Report Date:	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Newfield proposes to extend the Application for Permit to Drill this well.

**Approved by the
 Utah Division of
 Oil, Gas and Mining**

Date: November 18, 2013

By: 

NAME (PLEASE PRINT) Mandie Crozier	PHONE NUMBER 435 646-4825	TITLE Regulatory Tech
SIGNATURE N/A	DATE 11/12/2013	



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43013508980000

API: 43013508980000

Well Name: GMBU 1-2-9-15H

Location: 0987 FNL 0747 FEL QTR NENE SEC 02 TWNP 090S RNG 150E MER S

Company Permit Issued to: NEWFIELD PRODUCTION COMPANY

Date Original Permit Issued: 11/22/2011

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Mandie Crozier

Date: 11/12/2013

Title: Regulatory Tech **Representing:** NEWFIELD PRODUCTION COMPANY

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-43538
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
1. TYPE OF WELL Oil Well		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		8. WELL NAME and NUMBER: GMBU 1-2-9-15H
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		9. API NUMBER: 43013508980000
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0987 FNL 0747 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 02 Township: 09.0S Range: 15.0E Meridian: S		9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
		COUNTY: DUCHESNE
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 11/22/2014	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: <input type="text"/>
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Newfield proposes to extend the Application for Permit to Drill this well.

Approved by the
November 10, 2014
Oil, Gas and Mining

Date: _____

By: 

NAME (PLEASE PRINT) Mandie Crozier	PHONE NUMBER 435 646-4825	TITLE Regulatory Tech
SIGNATURE N/A		DATE 11/5/2014



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43013508980000

API: 43013508980000

Well Name: GMBU 1-2-9-15H

Location: 0987 FNL 0747 FEL QTR NENE SEC 02 TWNP 090S RNG 150E MER S

Company Permit Issued to: NEWFIELD PRODUCTION COMPANY

Date Original Permit Issued: 11/22/2011

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Mandie Crozier

Date: 11/5/2014

Title: Regulatory Tech **Representing:** NEWFIELD PRODUCTION COMPANY



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

December 11, 2014

Newfield Production Company
Rt. 3 Box 3630
Myton, UT 84052

Re: APDs Rescinded for Newfield Production Company
Uintah and Duchesne County


Ladies and Gentlemen:

Enclosed find the list of APDs that is being rescinded. No drilling activity at these locations has been reported to the division. Therefore, approval to drill these wells is hereby rescinded.

A new APD must be filed with this office for approval prior to the commencement of any future work on the subject location.

If any previously unreported operations have been performed on this well location, it is imperative that you notify the Division immediately.

Sincerely,


Diana Mason
Environmental Scientist

cc: Well File
SITLA, Ed Bonner
Brad Hill, Technical Service Manager



43-013-50904 Condor Trust 13-18-4-1W
43-013-50889 Deep Creek 4-17-4-1W
43-047-51753 Alderson 12-23-4-1W
43-013-50895 Close 12-16-4-1W
43-013-50937 Allred 9-13-4-2W
43-013-50938 Nephi Moon 11-9-4-2W
43-013-50939 Nephi Moon 12-9-4-2W
43-013-50942 Nephi Moon 13-9-4-2W
43-013-50943 Nephi Moon 14-9-4-2W
43-013-50898 GMBU 1-2-9-15H
43-013-50959 GMBU 1-16-9-17H
43-013-50968 GMBU 3-2-9-15H